



Town Hall Drywall, Inc.

3720 Skypark Drive, Torrance, CA 90505
Tel (310) 991-4462 · Fax (310) 378-1931

Heat Illness Prevention Plan

Town Hall Drywall

Protect your employees working in high heat.
(T8CCR) section 3395

DISCLAIMER:

This program is offered in good faith and is believed to be accurate and reliable at the time of completion. However, the program is made without warranty, claims, or guarantees as to its accuracy or the completeness, either expressed or implied, as to its condition or fitness for a particular purpose, merchantability, or any other matter. M Squared Safety, LLC assumes no liability for any loss, whether direct, indirect, special, consequential, exemplary, incidental, or of any kind or for any reason whatsoever arising out of its use.

Heat Illness Prevention Plan

Town Hall Drywall

Overview and Objectives

This Heat Illness Prevention Plan (HIPP) applies to employees of Town Hall Drywall, who work in outdoor areas of employment or on job tasks where the environmental risk factors for heat illness are present and are at risk for developing heat illnesses if they do not protect themselves appropriately. Based on the Code of Regulations Proposed State Standard, Title 8, and Section 3395*, this standard applies to all outdoor places of employment, with the following industries being subject to all provisions of the standard:

- Agriculture**
- Construction
- Landscaping
- Oil & Gas Extraction
- Transportation or delivery of agricultural products, construction materials or other heavy materials unless operating an air-conditioned vehicle that does not include loading or unloading.

Scope

The Town Hall Drywall HIPP includes steps for ensuring drinking water is provided in sufficient amounts, temperatures and humidity conditions are monitored, shade is available as required by the law, high heat procedures are followed, employee training is in place, emergency response procedures are documented, acclimatization of employees is accounted for, and auditing processes are incorporated to strengthen the plan's success.

Policy

It is the policy of Town Hall Drywall that any employee participating in job tasks where environmental risk factors for heat illness are present will comply with the procedures in this document and in the Injury and Illness Prevention Program. A copy of this Heat Illness Prevention Plan will be made available at each job site.

Water

Town Hall Drywall will provide fresh, pure, and suitable cool water, free of charge, as close as practicable to areas where employees are located. Foremen will visually examine the water to ensure purity and check that it is adequately cool by pouring some on their skin.

When employees are working in large areas water will be placed in several locations. Town Hall Drywall will also place water in designated shade areas and near restrooms. Town Hall Drywall will ensure that 1 quart of water per person per hour is available at the start of the shift and will have a water replenishment system (including designated responsibility) in place. Town Hall Drywall encourages employees to drink water frequently and to report low water levels, as well as warm or dirty water containers, to Foremen.

Procedures for Monitoring the Weather

Foremen will be trained and instructed to check in advance the extended weather forecast. Weather forecasts can be checked with the aid of the internet (<http://www.nws.noaa.gov/>), by calling the National Weather Service phone numbers (see CA numbers below), or by checking the Weather

Channel TV Network. The work schedule will be planned, taking into consideration whether high temperatures or a heat wave is expected. Routine advance weather monitoring will take place between the months of May and September; with additional advance monitoring conducted as needed during the remainder of the year.

In addition to advance weather monitoring, Foremen shall utilize one of the aforementioned weather services to review the day's forecasted temperature and humidity level prior to the start of work. Temperature and humidity levels will also be monitored on the work site throughout the day and compared to the National Weather Service Heat Index to evaluate the risk level for heat illness and determine when precautionary heat illness prevention measures should be taken. Temperature will be monitored by means of onsite thermometers in degrees Fahrenheit or by calling the numbers provided below. Temperature measurements will be taken in work areas where shade is not present.

California Dial-A-Forecast

- Eureka 707-443-7062
- Hanford 559-584-8047
- Los Angeles 805-988-6610 (#1)
- Sacramento 916-979-3051
- San Diego 619-297-2107 (#1)
- San Francisco 831-656-1725 (#1)

Shade

Town Hall Drywall will provide shade when the temperature exceeds 80 degrees Fahrenheit. Shade areas will be open to the air or provided with ventilation or cooling. Enough shade will be provided to accommodate the number of employees on break or recovery period at any given time.

Town Hall Drywall will ensure that employees in shaded areas can sit in a normal posture fully in the shade without having contact with one another. The shade shall be located as close as practicable to the work area. During meal periods, the amount of shade available shall be enough to accommodate the number of employees on meal break and those seeking cool-down rest periods.

Town Hall Drywall will encourage employees to take a preventive cool-down rest in the shade when they feel the need to protect themselves from overheating.

Employees taking cool-down breaks will be monitored and asked if they are experiencing symptoms of heat illness and will be encouraged to remain in the shade until any signs or symptoms have abated. Employees will be given no less than 5 minutes to rest in the shade, in addition to time needed to access the shade.

Town Hall Drywall policy will be that any employee who exhibits signs or reports symptoms of heat illness while taking a preventive cool-down rest shall be provided with appropriate first aide or emergency response.

High Heat Procedures

Town Hall Drywall will implement the following high heat procedures when the temperature equals or exceeds 95 degrees Fahrenheit.

- A supervisor, or a qualified designee, shall directly observe employees, for signs and symptoms of heat illness. Each supervisor, or qualified designee, shall be responsible for observing no more than 20 employees.
- If impractical to directly observe employees, a mandatory buddy system shall be implemented or;

- Regular communication with employees working solo shall be implemented by either radio or cellular phone or;
- Other effective observation such as periodic checks.
- Employees shall be observed for symptoms of heat illness and will be reminded throughout the work shift to drink plenty of water.
- Town Hall Drywall will designate 1 or more employees to call for emergency medical procedures, and will allow any employees to call for emergency services when a designated person is not available.
- Town Hall Drywall will closely supervise new employees for the first 14 days of employment, unless the new employee indicates at the time of hire that they have been doing similar work for at least 10 of the past 30 days, and for more than 4 hours per day.
- When temperatures reach 95 degrees or above, Town Hall Drywall will ensure that an employee takes a minimum 10-minute preventive cool-down rest period every 2 hours. The preventive cool-down rest period may be provided concurrently with any other required meal or other rest period.
- When the workday extends beyond 8-hours, Town Hall Drywall will provide an additional preventive cool-down period at the conclusion of the 8th hour of work. If the workday extends beyond 10 hours, then another preventive cool-down rest period will be provided at the conclusion of the 10th hour of work, and so on until the end of the work day.
- Town Hall Drywall will provide a pre-shift meeting during periods of high heat to remind employees:
 1. Of the company's high heat procedures.
 2. To drink plenty of water.
 3. Of their right to take cool-down rest periods when necessary.

Training

Town Hall Drywall will provide training to all Foremen, and affected employees, prior to their engaging in work that could result in exposure to risk factors for heat illness. Training will include:

- An explanation of the employer's responsibility to provide shade, water, cool-down rest periods, and access to first aide, as well as the employee's right to exercise their rights without fear of retaliation.
- Environmental and personal risk factors for heat illness.
- The signs and symptoms of heat illness.
- The importance of immediately reporting signs and symptoms of heat illness – and appropriate first aide to be taken.
- Importance of frequent consumption of water.
- Importance of acclimatization.
- Town Hall Drywall response plan to a case of possible heat illness.
- Supervisor and employee responsibilities.
- Foremen will be taught procedures to follow in case of an employee reporting or displaying symptoms of heat illness.
- Foremen will be trained how to monitor weather reports and how to respond to hot weather advisories.

Emergency Response Procedures

All Foremen and management personnel of Town Hall Drywall are required to take immediate action if an employee exhibits signs or symptoms of heat illness. Emergency response procedures will include but not be limited to the following actions:

- Ensuring that effective communication by voice, observation, or electronic means are maintained so that employees at the high temperature work site can contact a supervisor or emergency medical service when necessary.

- Cellphones, company radio, email and other electronic devices will be used for communication. If electronic devices are not reliable forms of communication, Town Hall Drywall will develop alternative means of summoning emergency medical services.
- Employers and Foremen will be trained to recognize symptoms of heat stress, such as decreased level of consciousness, disorientation, irrational behavior, staggering, vomiting and convulsions; and are required to take immediate action if any employee exhibits signs of the mentioned symptoms of heat illness.
- Foremen and employees will be taught first aide measures and how emergency services are to be provided to affected employees.
- Employees exhibiting signs or symptoms will be monitored and shall not be left alone or sent home without being first offered onsite first aid and /or being provided with emergency medical service.
- If deemed necessary, emergency medical services will be contacted, and employees will be transported to a place where they can be reached by emergency medical providers.
- In emergency events – clear and precise directions to the work site will be provided to emergency responders.
- In the event that a work site is in a difficult to find location, an employee will be sent to meet emergency medical services at the nearest landmark; and lead them to the work site.

Acclimatization

- New employees and employees who have not previously worked in environments where the possibility that heat illness may occur will be given an opportunity for their bodies to gradually be exposed to heat. Employees will be given an opportunity to adapt to the heat by working in the heat for at least 2 hours a day, between 4 to 14 days.
- Town Hall Drywall will also monitor employees during a heat wave. “Heat wave” being defined as any day the predicted temperature is at least 80 degrees Fahrenheit and at least 10 degrees Fahrenheit higher than the average high daily temperature in the preceding 5 days. Monitoring can be done by either the supervisor or by use of the buddy system.
- Town Hall Drywall will stress to new employees the importance of immediately reporting to their supervisor symptoms and signs of heat stress in themselves or in co-workers.

Heat Illness Prevention Plan Audit

Town Hall Drywall, as part of the implementation of our Injury & Illness Prevention Program, and to ensure the success of our HIPP, will conduct an audit of our written plan and documentation by Foremen and Managers. Audits of the Written HIPP will be conducted periodically, or when standards change. The audit shall review the plan to ensure that the heat illness prevention procedures continue to be effectively implemented. HIPP will be audited during each onsite safety inspection in addition to the annual audit of the entire program. This will include, but is not limited to:

- Ensuring that suitably fresh and cool water is routinely provided in the required amounts.
- Ensuring sufficient shade is routinely made available.
- Verifying that the required supervisor and employee training has been completed.
- A review of the effectiveness of emergency response procedures.
- Ensuring that employees are acclimatized as required.
- Ensuring that high heat procedures are implemented when the temperature reaches 95 degrees Fahrenheit.

Heat Illness Prevention Plan Site Specific

Town Hall Drywall, as part of the implementation of our Injury & Illness Prevention Program, and to ensure the success of our HIPP, will have a Site-Specific Heat Illness Prevention Addendum Form completed for jobs to ensure Foremen are implementing the required elements of the HIPP properly.

Site-Specific Heat Illness Prevention Plan

Town Hall Drywall

Date: _____

Job Name: _____

Job Site Address: _____

Foremen / Lead: _____

**Temperature Measuring
Device:** _____

Morning Temperature: _____

**Afternoon
Temperature:** _____

**Responsible Person in
Charge of Water
Replenishment:** _____

**Water Replenishment
Location:** _____

Shade Location: _____

**Emergency Response
Person:** _____

Additional Notes: _____
